

BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of the work: Resetting of Chainlink Fencing implimentaion of rainwater harvesting and implimentaion to park at CQAL park in ward No.8.

Sl. No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
1	1.00	Providing ,fabricating and fixing Special Multiplay Systems consists of FRP moulded with Aluminium chequered platforms of size 5x5 ft with 4 support pillar made out of 75 mm dia G.I "B" pipes fixed in cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be with tubular slide & Mini Aquva tunnel Slide made up of high quality FRP the slide is to fixed at a height of 11ft and runs for a length of not less than twenty ft and the slide should be supported at regular intervals of 6ft using M.S pipes support and the platform ladder with 25mm dia MS pipes with suitable hand rails and steps made out of G I sheet with tred 4" with powder coated finish, fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-corrossive ,fade free,tough grade,durable hard and should prevent uv light. The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift, loading and unloading and any incidental charge required for it	Each	560000.00	Rupees Five Hundred Sixty Thousand Only
2	1.00	Providing, fabricating and fixing of spiral climber of height not less than 10ft made out of 25mm dia MS pipe with Aluminium chequered plate platform of size 3x3 ft with 4 legs made out of 75mm dia G.I pipe fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be fitted with single lane slide made up of high quality FRP the slide is fixed at a height of 9 ft and runs for a length of not less than 20ft the slide should be supported at regular interval of 4 ft using M.S pipes support powder coated, fine quality FRP with suitable design and as per drawing platforms should be placed at approximately 9 ft from ground level. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specification and directions of the engineer in charge of the all lead and lift, loading and un loading and any incidental charges required for the successful completion of the work (ALL FRP items are gel water finish or stoving paint in ovens)	Each	160000.00	Rupees One Hundred Sixty Thousand Only
3	1.00	Providing, fabricating and fixing play equipments consisting of the platform with 65mm dia MS pipe & Aluminium chequered plates of size 3x3 ft fixed at 7 ft height from ground level with 4 legs made out of 75mm dia G.I pipes fixed cement concrete 1:2:4 The platforms are to be covered with pyramid shaped FRP roof, the slide should be supported at regular intervals of 4ft using M.S pipes support powder coated, fine quality FRP with suitable design and as per drawing. The play equipment is to be fitted with Double seated swing for kids and Aqua bowl slide made up of high quality FRP the slide is to fixed at a height of 7 ft and runs for length of not less than 12ft .Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light .The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successssful completion of the work (All FRP items are gel water finish or stoving paint in ovens)	Each	200000.00	Rupees Two Hundred Thousand Only
4	1.00	Providing fabricating and fixing Special play equipments consisting of the plat form with 65mm dia MS pipe and Aluminium chequered plates of size 3x3 ft fixed at 5 ft heiht from ground level with 4 legs made out of 65mm dia G.I "B" class pipe fixed cement concrete 1:2:4 The plat forms are to be covered with pyramid shape FRP roof. The platforms is to be fixed with MOnkey Climber for kids and Roller Slide(Moulded plastic rollers) fixed at a height of 5 ft and runs for a length of not less than 12 ft the slide should be supported at regular intervals of 6ft using MS pipes support powder coated fine quality FRP with suitable design as per drawing Mould FRP slides are non-Corrossive fade free , tough grade, durable hard and should prevent UV light .The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work (All FRP items are gel water finish or stoving paint in ovens)	Each	160000.00	Rupees One Hundred Sixty Thousand Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
Signature of the Contractor

Signature of the Contractor

26/02
Executive Engineer

S.No.	Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
5	1.00	Providing fabricating and fixing Children play equipments consisting of the plat form with 65mm dia MS pipe and Aluminium chequered plates of size 3x3 ft and 3 ft height from ground level with 4 legs made out of 75mm dia G.I pipe fixed cement concrete 1:2:4 The plat forms are to be covered with pyramid shape FRP roof. fine quality FRP with suitable design and as per drawing .The platforms is to be fitted with Double twin wave slide for kids made up of high quality FRP material and also high quality plastic rope climber is to fixed at a height of 3 ft and runs for a length of not less than 5 ft moulded FRP slides are non corrosive, non-Corrosive fade free ,tough grade,durable hard and should prevent UV light. Thework should be executed as per standerd specification and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successssful completion of the work (All FRP items are gel water finish or stoving paint in ovens)	Nos	125000.00	Rupees One Hundred Twenty Five Thousand Only
6	1.00	Providing fabricating and fixing Multiplay Special slider systems consisting of the plat form with 25mm dia MS pipe and Aluminium chequered plates of size 3x3 ft fitted at 7 ft height from ground level with 4 legs made out of 65mm dia G.I pipes fixed cement concrete 1:2:4. The plat forms is to be fitted with FRP wave slide spiral slide and standard slide with vertical ladder on one side each with GI sheet steps of treads 4" 25mm dia MS pipes with suitable Hand rails fixed at a height of 5 ft and runs for a length of not less than 12 ft the platforms are to be coverd with rramid Shape FRP roof this slide should be supported at regular intervals of 4 ft using MS pipes support powder coated fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-Corrosive fade free ,tough grade ,durable hard and should prevent uv light.The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift,loading and unloading and any incidental charges required for the successful competion of the work	Unit	480000.00	Rupees Four Hundred Eighty Thousand Only
7	1.00	Providing and fixing childern play bridge with MS perforated tunnel and wave bridge and Arch bridge and hanging bridge made out of MS pipe and chequered plates uns for a height 11 ft to 5 ft the work should be executed as per the standard specification and direction of the engineer in charge of the with all lead and lift ,loading and unloading and any incidenteial charges required for the successful competion of work (all swings chains are rubber coated &all 'S' hooks are stainless steel)	Each	100000.00	Rupees One Hundred Thousand Only
8	4.00	Providing Rainwater harvesting pits for Parks	No's	21000.00	Rupees Twenty One Thousand Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

EXECUTIVE ENGINEER-4
CONTRACTOR
KRIDL, BBMP DIVISION
BENGALURU-560 010